## Malletts Bay Transportation Scoping Study Project Evaluation Matrix: West Lakeshore Drive Bicycle & Pedestrian Improvements

				Alt. 3	Alt. 4	Alt. 4A		Alt. 4C
		Alt. 1	Alt. 2	Bike Lanes	Shared Use Path	Alt. 4 + Section at Water	Alt. 4B	Alt. 4 + North side path at
		No Build	Shared Use Lanes	(both sides of road)	(south side of road)	Elevation	Alt. 4 + Overlook Area	western end
	Engineering Design <sup>+</sup>	\$0	\$10,000	\$80,000	\$220,000	\$250,000	\$290,000	\$250,000
	Roadway/Path Construction	\$0	\$20,000	\$510,000	\$1,300,000	\$1,550,000	\$1,420,000	\$1,600,000
	Stormwater Improvements (Meets Standards)	\$0	\$0	\$900,000	\$900,000	\$900,000	\$900,000	\$900,000
	Stormwater Improvements (Exceeds Standards)	\$0	\$0	\$2,400,000	\$2,400,000	\$2,400,000	\$2,400,000	\$2,400,000
Costs	Retaining Wall, Railing & Stairs Construction	\$0	\$0	\$0	\$0	\$50,000	\$1,780,000	\$0
ů	Resident (Construction) Engineering	\$0	\$0	\$40,000	\$130,000	\$160,000	\$130,000	\$160,000
	Water line Relocation Cost	\$0	\$0	\$0	\$2,500,000	\$2,500,000	\$2,500,000	\$2,500,000
	Total (Meets Standards, Not including ROW)	\$0	\$30,000	\$1,530,000	\$5,050,000	\$5,410,000	\$7,020,000	\$5,410,000
	Total (Exceeds Standards, Not including ROW)	\$0	\$30,000	\$3,030,000	\$6,550,000	\$6,910,000	\$8,520,000	\$6,910,000
		11' travel lanes	11' travel lanes		11' travel lanes	11' travel lanes	11' travel lanes	11' travel lanes
	Typical Section	1-3' paved shoulder	1-3' paved shoulder	11' travel lanes	1-3' paved shoulders	1-3' paved shoulders	1-3' paved shoulders	1-3' paved shoulders
		5' sidewalk	5' sidewalk	5' bike lanes	10' paved shared use path			
	Bicycle Access	-	Shared use lanes	5' bike lanes	Adds shared use path			
δ					Improved for Path Users			
Engineering					(Bicyclists and pedestrians are			
ne	Pedestrian Safety	-	No Change	No Change	given more room and separated			
igi					from vehicles)	from vehicles)	from vehicles)	from vehicles)
ū						from venicies)		from venicles/
				Slight Improvement	Improved	Improved	Improved	Improved
	Vehicle Safety	-	No Change	Bikes are given a facility	Bikes are on a separated facility	Bikes are on a separated facility	Bikes are on a separated facility	Bikes are on a separated facility
				separate from vehicle lanes	off of the roadway			
	DOW/ Imposts		Na	-	Madavata		Madavata	
	ROW Impacts	-	No	No	Moderate	High	Moderate	Moderate
	Agricultural Lands	-	No	Potential	Potential	Potential	Potential	Potential
	Archaeological	-	No	No	No	No	No	No
	Historic	-	No	No	No	No	No	No
	Hazardous Materials	-	No	No	No	No	No	No
	Floodplains	-	No	No	No	Yes	Potential	No
	Shoreland	-	No	No	No	Yes	Potential	No
	Fish & Wildlife	-	No	No	No	No	No	No
ts	Rare, Threatened & Endangered Species	-	No	No	No	Potential	Potential	No
Impact	Public Lands - Sect. 4(f)	-	Yes	Yes	Yes	Yes	Yes	Yes
Ĕ	LWCP - Sect. 6(f)	-	No	No	No	No	No	No
-	Managed Lands	-	No	No	No	No	No	No
	Noise	-	No	No	No	No	No	No
	Wetlands	-	No	No	Yes	Yes	Yes	Yes
	New Impervious Surfaces	-	No	Yes - 13% New	Yes - 17% New	Yes - 21% New	Yes - 24% New	Yes 24% New
			Moderate	Low				
	Stormwater Accommodations	None	(Narrow green belt for	(Narrowed greenbelt does not	Moderate	Moderate	Moderate	Moderate
			bioswales)	accommodate bioswales)	(Narrow green belt for bioswales)	(Narrow green belt for bioswales)	(Narrow green belt for bioswales)	(Narrow green belt for bioswales)
	Aesthetics	-	No impacts	Minimal	Improved	Improved w/ Water Views	Improved w/ Water Views	Improved
ak	Community Character	-	No impacts	Minimal	Improved	Improved	Improved	Improved
Local & Regional	Economic Impacts	-	No impacts	Minimal	Positive	Positive	Positive	Positive
egi	Conformance to Reg. Transp. Plan	-	Potential	Yes	Yes	Yes	Yes	Yes
- ~	Compliance With Current Zoning	-	Yes	Yes	Yes	No*	No*	Yes
	Satisfies Purpose & Need	No	No	Partial	Yes	Yes	Yes	Yes
	Act 250	-	No	No	Potential	Potential	Potential	Potential
	Section 404 - Wetlands (USACOE)	-	No	No	Yes	Yes	Yes	Yes
	Section 401 Water Quality Certification	-	No	No	Yes	Yes	Yes	Yes
	State Wetlands Permit	-	No	Yes	Yes	Yes	Yes	Yes
	Stream Alteration Permit	-	No	No	No	No	No	No
S			Nie	Yes	Yes	Yes	Yes	Yes
mits	Construction Phase Storm Water Discharge Permit	_	INO		103	163	165	103
Permits	(General Permit 3-9020)	-	No	Tes				
Permits	(General Permit 3-9020) Operational Phase Storm Water Discharge Permit	-				Υρς	Yes	Yes
Permits	(General Permit 3-9020) Operational Phase Storm Water Discharge Permit (General Permit 3-9015)	-	No	Yes	Yes	Yes	Yes	Yes
Permits	(General Permit 3-9020) Operational Phase Storm Water Discharge Permit (General Permit 3-9015) Lakes & Ponds	-	No	Yes	Yes	Potential	Potential	No
Permits	(General Permit 3-9020) Operational Phase Storm Water Discharge Permit (General Permit 3-9015)		No	Yes	Yes			

\* - Not compliant with current zoning as written. May be approved after Town review